# **Prequalified List**

# TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL SYSTEMS March 11, 2022 This list supersedes the March 26, 2021 list. Standard Specifications for Road and Bridge Construction, Section 522

For information regarding new System submittals, click the "New Submittal" bookmark to the left.

Sanders Pre-Cast Concrete Systems Co 6051 South Indianapolis Rd Whitestown, Indiana 46075 Date Approved: Dec 23, 2010 Contact Name: Mark Sanders Phone Number: 800-769-5503 Systems: "Sanders Wire Wall System"	Shaw Technologies 6101 Long Prairie Road, Suite 744-126 Flower Mound, TX 75028 Date Approved: Contact Name: Larry Shaw Phone Number: 817-247-4301  Systems: "Temporary MSE"
Elevate Infrastructure, LLC 2495 W Bungalow Rd Morris, IL 60450 Date Approved: Aug 2021 Contact Name: Matt Austin Phone Number: 636-346-9245  Systems: "Elevate Temporary MSE Wall System"	SSL Construction Products 4740 Scotts Valley Dr, Suite E Scotts Valley, Ca 95066 Date Approved: 2006 Contact Name: Andrew Meckler Phone Number: 831-430-9300  Systems: "MSE Plus Wire Face"
Vist-A-Wall Systems (Contech Engineered Solutions) 650 Justice Lane Mansfield, TX 76063 Date Approved: Contact Name: Chris Staud Phone Number: 817-507-0454  Systems: "Vist-A-Wire Wall"	Tensar International Corp 2500 Northwinds Pkwy, Suite 500 Alpharetta, GA 30009 Date Approved: 2007 Contact Name: Vicky C-Curtis Phone Number: 770-344-2090  Systems: "Tensar Temporary"

### **Prequalified List**

# TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL SYSTEMS March 11, 2022

This list supersedes the March 26, 2021 list.

Standard Specifications for Road and Bridge Construction, Section 522

For information regarding new System submittals, click the "New Submittal" bookmark to the left.

Reinforced Earth Co

1444 North Farnsworth Avenue

Suite 505

Aurora, IL 60505 Date Approved:

Contact Name: Alex Abraham Phone Number: 630-898-3334

Systems:

"Terratrel"

Tricon Precast, LLC

15055 Henry Road Houston, TX 77060

Date Approved: Sept 30, 2013 Contact Name: Bryan Jennings Phone Number: 877-387-4266

Systems:

"Tricon Temporary Wire"

#### Domestic Steel Act Applies:

All iron and steel products, which are to be incorporated into state projects shall be domestically manufactured or produced and fabricated. The Contractor shall obtain from the iron or steel producer and/or fabricator, in addition to the mill analysis, a certification that all iron or steel materials meet these domestic source requirements. The application of all coatings, epoxy, galvanizing, painting, etc., to metal products shall be domestically applied.

### **Pregualified List**

# TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL SYSTEMS March 11, 2022

This list supersedes the March 26, 2021 list.

Standard Specifications for Road and Bridge Construction, Section 522

For information regarding new System submittals, click the "New Submittal" bookmark to the left.

### Submittal Requirement for Evaluation and Pre-Qualification

## A. Scope

Before a TMSE retaining wall system can be used on a Department project, the system shall be reviewed and pre-qualified for general use, and the manufacturer/supplier shall have a producer/supplier number assigned to their facility. The following guidelines are provided to clarify the submittal requirements and expedite the process.

### B. Procedure

Companies interested in being considered pre-qualified to supply a TMSE retaining wall system as specified in Section 522 of the Standard Specifications for Temporary Mechanically Stabilized Earth Retaining Walls shall provide two copies of a system review package to the Department for evaluation. As a minimum, the system review package should contain the following:

- Acknowledgement by Company (Form <u>BMPR 101</u>). If your company does not already have a
  product included on an IDOT QPL, please submit a signed copy of the company
  acknowledgement form with your product submittal.
- Wall System name and company name to be listed on the specification and other contact/address information.
- Any independent evaluation information or other supporting research if available.
- A list of past projects which used your company wall system, including owner's name and phone number.
- Typical shop drawings, notes and plan details including:
  - All facing types and details
  - All soil reinforcement types and details
  - o Connection details for soil reinforcement to the temporary facing.
  - Select Reinforced Backfill Requirements.
  - Typical details of soil reinforcement placement around appurtenances located behind, on top of, or passing through the soil reinforced wall volume.
  - Acute corner facing and reinforcement details.
- Design Standards and Computations: All example computations for the wall design and the soil reinforcement embed/facing connections, shall be sealed by an Illinois Licensed Structural Engineer and shall be according to the latest AASHTO LRFD Bridge Design Specifications and Section 522 of the Standard Specifications for Temporary Mechanically Stabilized Earth Retaining Walls. As a minimum, the following should be addressed:
  - Corrosion reduction calculations or Geosynthetic reductions.
  - Pullout capacity calculations for all soil reinforcement types.
  - If a computer program will be provided as calculations, explanation of how each value is determined must be provided with an example computer printout.
  - Reinforcement max stress calculations.
  - Bearing pressure calculations.
  - All materials design stress assumptions.
  - o Any design limitations such as maximum wall height, etc.
- Any test data or research to support the computations and use of specific values.

### **Pregualified List**

# TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL SYSTEMS March 11, 2022

This list supersedes the March 26, 2021 list.
Standard Specifications for Road and Bridge Construction, Section 522

For information regarding new System submittals, click the "New Submittal" bookmark to the left.

### Submittal Requirement for Evaluation and Pre-Qualification, continued

- All materials specifications.
- A Construction Manual with erection sequence guidance required for proper alignment and wall performance.
- Any design manuals, case histories, and brochures should be included to provide insight into the system and applications.

Two copies of the system review package shall be submitted to:

Illinois Department of Transportation Bureau of Bridges and Structures Attn: Design Section 2300 South Dirksen Parkway Springfield, IL 62764

If you have any questions concerning the specification or the requested information, please contact the Policies, Standards and Specifications Unit at 217-782-9109 or 217-785-2914.

## C. Recertification

There is no renewal process or reapplication process to stay on this list; however the Department reserves the right to remove any system based on past performance. In addition, it is the responsibility of the manufacturer/supplier to inform the Department of any changes in design or component information, and contact information, etc. If it is discovered that changes have been made without informing the Department, the Department reserves the right, depending on the severity of the omission, to remove that system from the pre-qualified list.

Presence on this list does not exempt the manufacturer/supplier from meeting all the job specific submittal requirements and all the material requirements specified including component testing and/or material certifications as applicable.